BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50602

Name of Work: Maintenance of Footpath in Dasarahalli W.No 15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri B K NAGENDRA	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Dismantling of existing structures like culverts, Cum bridges, retaining walls and other structure comprising of masonry, cement concrete,-wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. Prestressed/Reinforced cement concrete grade M-20 above.	Cum	51.84	1414.5	Rupees One Thousand Four Hundred Fourteen and Fifty Paise Only
2	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification.	Cum	175.26	269.3	Rupees Two Hundred Sixty Nine and Thirty Paise Only
3	Providing and laying in position plain cement concrete of mix1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	7.02	4541.73	Rupees Four Thousand Five Hundred Forty One and Seventy Three Paise Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

4	:Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications.	Sqm	187.20	672.09	Rupees Six Hundred Seventy Two and Nine Paise Only
5	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6	Cum	56.70	5037.27	Rupees Five Thousand Thirty Seven and Twenty Seven Paise Only
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (TMT bars FC 500)	Tonne	1.12	77817.56	Rupees Seventy Seven Thousand Eight Hundred Seventeen and Fifty Six Paise Only
7	Providing and and fixing Precast Concrete slab 100 MM thick witth all lead and lift as per specification	Sqm	39.00	1962.61	Rupees One Thousand Nine Hundred Sixty Two and Sixty One Paise Only
8	Providing and and fixing Precast Concrete slab 250 MM thick witth all lead and lift as per specification	Sqm	161.70	4401.39	Rupees Four Thousand Four Hundred One and Thirty Nine Paise Only
9	Transportaion & disposing of the excavated earth obtained from side drains & high burns an either sides of the road 2km lead	Cum	227.10	71.93	Rupees Seventy One and Ninety Three Paise Onl

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Executive
Dasarahal